

## Memorandum

#### AGENDA ITEM 8

| DATE: | November 15, 2019 |
|-------|-------------------|
|-------|-------------------|

- **TO:** Transportation Authority Citizen Advisory Committee
- **FROM:** Eric Cordoba Deputy Director for Capital Projects Anna LaForte - Deputy Director for Policy and Programming
- SUBJECT: 12/10/19 Board Meeting: Allocate \$3,330,000 in Prop K Sales Tax Funds, with Conditions, to San Francisco Public Works for Better Market Street 5<sup>th</sup> to 8<sup>th</sup> Streets Design and Bikeway Pilot

#### **RECOMMENDATION** $\Box$ Information $\boxtimes$ Action

Allocate \$3,330,000 in Prop K funds, with conditions to San Francisco Public Works (SFPW) for Better Market Street (BMS) 5<sup>th</sup> to 8<sup>th</sup> Street Design and Bikeway Pilot

#### SUMMARY

Led by SFPW, the BMS project is comprised of various streetscape enhancements, transit capacity and reliability improvements, and state of good repair infrastructure work along a 2.2-mile stretch of Market Street between Steuart Street and Octavia Boulevard. It includes construction of sidewalk-level bicycle lanes, pavement renovation, utilities relocation and upgrades, turn restrictions implementation, and improvements on sidewalk; way-finding; lighting; landscaping; transit boarding islands; transit connections; and traffic signals. The preliminary cost estimate for all phases of the project is \$604 million. SFPW has developed a proposed phasing plan that could enable construction of Phase 1A (the segment between 5th and 8th streets) to start in late 2020, pending funding availability. Last month, relevant city agencies took the required CEQA approval actions. The 30day appeal period ended on November 12 and no appeals were filed. The subject request includes \$1.1 million for installation and evaluation of a pilot sidewalk level bikeway along the south side of Market Street between Gough and Franklin streets. The remaining \$2.23 million is to complete design of Phase 1A. The current estimated Phase 1A construction cost is \$178 million, a \$51 million increase from the previous estimate of \$127 million. The project team is seeking funding to fill a \$35 million gap in construction funds.

 $\boxtimes$  Fund Allocation

- □ Fund Programming
- □ Policy/Legislation
- $\Box$  Plan/Study
- ⊠ Capital Project Oversight/Delivery
- □ Budget/Finance
- □ Contract/Agreement

□ Other:



#### DISCUSSION

#### BACKGROUND.

**OBAG Reporting Condition:** As a condition of receiving OBAG funds, all project sponsors are required to provide quarterly progress reports to the Transportation Authority through our grants portal to assist with project delivery oversight and compliance with OBAG timely-use-of-funds requirements. In addition, the Board action programming OBAG funds to the BMS project required SFPW to provide quarterly reports and semi-annual updates on the project to the Board, addressing any changes in project schedule and cost, in particular.

**BMS:** Market Street is San Francisco's premier boulevard and an important local and regional transit corridor. The BMS project will completely reconstruct 2.2 miles of the corridor, from Steuart Street to Octavia Boulevard. It is a multi-modal project that includes among other features, a new sidewalk-level cycle track, pavement renovation, landscaping, Muni track replacement and a new F-Line loop that would enable the streetcars to turnaround along McAllister Street and Charles J. Brenham Place, providing increased operational flexibility.

To support its role as a transit, bike, and pedestrian corridor, the BMS project will prohibit the entry of vehicles on Market Street between Steuart and 9th streets, in the westbound direction, and Market Street between 10th and Main streets, in the eastbound direction, except for buses, taxis, bicycles, commercial vehicles, and emergency vehicles. BMS will also prohibit vehicle entry on Market Street between 9th and 12th streets, in the westbound direction, and between 12th and 11th streets, in the eastbound direction, except for Muni, AC transit, taxis, bicycles, and emergency vehicles. The intent of these changes is to allow space on Market Street to be allocated for pedestrians and bicyclists, thereby improving safety and health, prioritizing transit modes, providing for loading to support adjacent land uses, and improving Market Street as a civic space.

Although not part of the BMS project, the project team is coordinating with BART on its efforts to construct escalator canopies at BART/Muni entrances and to perform state of good repair work on BART ventilation grates.

In addition to its transportation-focused goals supporting the City's Transit First and Vision Zero policies, the project is also intended to help revitalize Market Street as the City's premier pedestrian boulevard.

The BMS project is a partnership between SFPW, which is the lead agency, the Transportation Authority, the San Francisco Municipal Transportation Agency (SFMTA), San Francisco Public Utilities Commission (SFPUC), and the Planning Department, which is leading the environmental review.

#### STATUS AND KEY ACTIVITIES.

Page 2 of 6



#### **Environmental Clearance and Preliminary Engineering.**

BMS completed environmental review under the California Environmental Quality Act (CEQA) but is still undergoing environmental review under the National Environmental Policy Act (NEPA). The San Francisco Planning Department issued the Draft Environmental Impacts Report for public circulation on February 27, 2019. The Planning Department accepted comments on the Draft EIR through April 15, 2019, and the Planning Commission held a public hearing on the Draft EIR on April 4, 2019. The project team received 59 comments from public agencies, organizations, and individual persons, which were primarily focused on transportation, including transit stops/bus boarding islands, loading, and vehicle access. The Planning Department prepared a response to comments received on environmental issues, and made minor text changes to the Draft EIR in a Responses to Comments document published on September 23, 2019. The San Francisco Planning Commission, on October 10, 2019, certified the Final EIR and found that the contents of the report and the procedures through which the report was prepared, publicized, and reviewed complied with the provisions of CEQA. The 30-day appeal period ended at 5:00pm on November 12, 2019. No appeal was filed.

SFPW approved the project with the western variant and adopted the CEQA Findings, including a statement of overriding considerations, and the Mitigation Measure and Reporting Program on October 11, 2019. The SFMTA Board of Directors, on October 15, 2019, adopted the BMS Final EIR CEQA findings as its own, including the mitigation measures.

#### Project Phasing, Quick Build Auto Restrictions and Bikeway Pilot.

<u>Project Phasing.</u> Large projects such as BMS often are implemented in phases due to funding availability (both timing and amount) and a desire to minimize construction impacts and disruptions. The project team has identified Phase 1 as Market Street between 5th and 8th streets and is currently working on the detailed design for this phase. Phase 1 is further divided into Phase 1A, the full suite of improvements planned for BMS on the segment extending from 5<sup>th</sup> to 8<sup>th</sup> streets, and Phase 1B, the aforementioned F-Loop.

Pending funding availability, SFPW is proposing a phasing plan for design and construction that could allow them to advertise Phase 1A construction in Fall 2020 and begin construction by late 2020.

<u>Quick Build Auto Restrictions.</u> SFMTA may implement auto restrictions on Market Street as a quick-build enhancement starting in Spring 2020 to increase safety on this High Injury Network street. Quick-build projects are reversible, adjustable traffic safety improvements that can be installed relatively quickly. The quick-build portion, if implemented, will prohibit cars on eastbound Market Street between 10th to Main Street, and on westbound Market Street from The Embarcadero to 11th Street.



Page 4 of 6

<u>Bikeway Separation Study and Pilot.</u> In summer 2019, the BMS team finished conducting a research study with people with mobility disabilities and people with visual disabilities to identify detectable tactile material that will be used for separation between bike lanes and pedestrian area as part of the proposal for sidewalk-level bikeway on the project. The study evaluated six different materials and the trapezoidal bar was recommended for implementation in the BMS project. This separation material is intended to improve safety for pedestrians with disabilities, and also help deter bicyclists from riding in the pedestrian zone. Although the team completed the materials study, they are still working on the report. The subject Prop K allocation request would fund installation of a pilot project on Market Street between Gough and Franklin streets in Spring 2020 to install asphalt sidewalk level bikeway, proposed ADA pavers and granite curb, and the detectable separation material recommended in the study. The pilot will include a before and after study and the results will be used to inform design of Phase 1A, along with the rest of the BMS project.

#### **Project Schedule.**

SFPW anticipates completion of final design for Phase 1A in Spring 2020 to allow advertisement for construction services in Fall 2020. Under this schedule, Phase 1A construction could start in late 2020, subject to full funding availability. Construction is anticipated to last until early 2023. This schedule also assumes NEPA certification in summer 2020.

A proposed schedule for design and implementation of the remaining segments of the BMS project is included as in the enclosed allocation request form. This schedule also assumes NEPA certification summer 2020 and is subject to funding availability.

As part of the July progress report update, we flagged that SFPW was concerned about schedule implications if the FTA were to take over as NEPA lead since FHWA had been lead to date. The potential change issue arose when the project was granted a \$15 million federal BUILD grant, administered by the FTA, for the new F-Loop streetcar turnaround. With the help of an OBAG fund exchange approved by the Board earlier this year, SFPW reports that this schedule risk has been eliminated as FHWA is the confirmed NEPA lead for the BMS project, including the F-Loop.

#### **Project Cost and Funding.**

The current estimated construction cost for Phase 1A is \$178 million which represents a \$51 million increase from the previous estimate of \$127 million, not including the F- Loop streetcar turnaround along McAllister Street and Charles J. Brenham Place in Phase 1B.

SFPW estimates Phase 1A construction cost of \$178 million and has committed funding from BART Measure RR, the federal BUILD grant program, OBAG, Prop K, and SFMTA's Prop A General Obligation bond. The project still needs to secure construction funding of \$36.5 million from SFPUC for utility works and an additional \$35.3 million in construction funding remains unidentified. The project team has identified additional Prop A General Obligation



Page 5 of 6

bond revenues as a potential fund source. The total Phase 1A cost, including soft costs, is \$220 million.

The total project cost estimate for all phases of the BMS project, based on 10% design, is \$604 million. Like most projects of this size at this stage of development, BMS has a significant funding gap which very little funding identified beyond Phase 1A. SFPW expects this estimate to change as detailed design of each construction phase progresses and as costs are updated to reflect escalation once schedule milestones are more certain. A significant portion of the total project cost represents state of good repair and infrastructure renewal work that would be required regardless of the BMS project.

#### **Current Issues and Risks.**

The BMS Project team is actively considering potential risks to the project scope, schedule, budget, and funding as the Phase 1A final design stages advance. The project team has potholed each block of Phase 1A to identify underground utilities and sub-sidewalk basements. Coordination with utility companies is on-going. When the BART tunnels were originally constructed under Market Street, BART developed detailed utility maps, thus there may be fewer utility conflicts and surprises when digging up and replacing sewer and water lines.

Larger trends also have the potential to impact the BMS project. A competitive construction environment exists across the Bay Area, resulting in construction bids on projects exceeding estimates developed in a slower market by close to 30%. Project cost engineers are aware of these challenges, and will be using the most up-to-date bids when developing the 100% cost estimate early next year. The project is not fully funded, and the shortfall may impact the schedule.

#### FINANCIAL IMPACT

The recommended action would allocate \$3,330,000 in Prop K funds. The allocations would be subject to the Fiscal Year Cash Flow Distribution Schedule contained in the attached Allocation Request Form.

Attachment 4 shows the approved Fiscal Year 2019/20 allocations and appropriations to date, with associated annual cash flow commitments as well as the recommended allocation and cash flow amount that are the subject of this memorandum.

Sufficient funds are included in the Fiscal Year 2019/20 budget to accommodate the recommended actions. Furthermore, sufficient funds will be included in future budgets to cover the recommended cash flow distribution for those respective fiscal years.

#### CAC POSITION

The CAC will consider this item at its November 20, 2019 meeting.



Page 6 of 6

#### SUPPLEMENTAL MATERIALS

- Attachment 1 Summary of Request Received
- Attachment 2 Project Description
- Attachment 3 Staff Recommendation
- Attachment 4 Prop K Allocation Summary FY 2019/20
- Attachment 5 Allocation Request Form

#### Attachment 1: Summary of Requests Received

|        |                                       |                                 |  |                              |   | Le  | veraging  |                         |             |
|--------|---------------------------------------|---------------------------------|--|------------------------------|---|---|---|-------------------------|-------------|
| Source | EP Line No./<br>Category <sup>1</sup> | Project<br>Sponsor <sup>2</sup> | Project Name   | Current<br>Prop K<br>Request | Total Cost for<br>Requested<br>Phase(s) | Expected<br>Leveraging by<br>EP Line <sup>3</sup> | Actual Leveraging<br>by Project Phase(s) <sup>4</sup> | Phase(s)<br>Requested   | District(s) |
| Prop K | 22U                                   | SFPW                            | Better Market Street - 5th to 8th Streets Design and Bikeway Pilot | \$ 3,330,000                 | \$ 18,600,000                           | 78%   | 82%   | Design,<br>Construction | 3, 5, 6     |
|        |                                       |                                 | TOTAL  | \$ 3,330,000                 | \$ 18,600,000                           | 78%   | 82%   |                         |             |

Footnotes

<sup>1</sup> "EP Line No./Category" is either the Prop K Expenditure Plan line number referenced in the 2019 Prop K Strategic Plan or the Prop AA Expenditure Plan category referenced in the 2017 Prop AA Strategic Plan, including: Street Repair and Reconstruction (Street), Pedestrian Safety (Ped), and Transit Reliability and Mobility Improvements (Transit).

<sup>2</sup> Acronym: SFPW (San Francisco Public Works)

<sup>3</sup> "Expected Leveraging By EP Line" is calculated by dividing the total non-Prop K funds expected to be available for a given Prop K Expenditure Plan line item (e.g. Pedestrian Circulation and Safety) by the total expected funding for that Prop K Expenditure Plan line item over the 30-year Expenditure Plan period. For example, expected leveraging of 90% indicates that on average non-Prop K funds should cover 90% of the total costs for all projects in that category, and Prop K should cover only 10%.

<sup>4</sup> "Actual Leveraging by Project Phase" is calculated by dividing the total non-Prop AA funds in the funding plan by the total cost for the requested phase or phases. If the percentage in the "Actual Leveraging" column is lower than in the "Expected Leveraging" column, the request (indicated by yellow highlighting) is leveraging fewer non-Prop K dollars than assumed in the Expenditure Plan. A project that is well leveraged overall may have lower-than-expected leveraging for an individual or partial phase.

#### Attachment 2: Brief Project Descriptions<sup>1</sup>

| EP Line No./<br>Category | Project<br>Sponsor | Project Name  | Prop K Funds<br>Requested | Project Description   |
|--------------------------|--------------------|---|---------------------------|---|
| 22U                      | SFPW               | Better Market Street - 5th to 8th<br>Streets Design and Bikeway Pilot | \$3,330,000               | The Better Market Street project is comprised of various streetscape enhancements, transit capacity and reliability improvements, and state of good repair infrastructure along 2.2 miles of Market Street between Steuart Street and Octavia Boulevard. Key features include a new sidewalk-level cycle track and a F-Line loop to enable streetcars to turnaound in the mid-Market area. Requested funds are for detailed design from 5th to 8th streets, which is anticipated to be complete by June 2020. The request also includes installation and evaluation of a pilot sidewalk level bikeway along the south side of Market Street between Gough and Franklin streets, which will be installed starting in March 2020 and be open for use by late July 2020. |
|                          | -                  | TOTAL   | \$3,330,000               |   |

<sup>1</sup> See Attachment 1 for footnotes.

#### Attachment 3: Staff Recommendations<sup>1</sup>


| EP Line<br>No./<br>Category | Project | Project Name  | Prop K Funds<br>Recommended | Recommendations  |
|-----------------------------|---------|---|-----------------------------|--|
| 22U                         | SFPW    | Better Market Street - 5th to 8th<br>Streets Design and Bikeway Pilot | \$ 3,330,000                | Deliverable: SFPW will present preliminary results of the bikeway pilot with the quarterly project update to the Board in Fall 2020.<br>Special Condition: The recommended allocation is contingent upon SFPW's continued compliance with quarterly project reporting on the Better Market Street project to the Transportation Authority Board, established as a condition of receiving OBAG funding. |
|                             |         | TOTAL   | \$3,330,000                 |  |

<sup>1</sup> See Attachment 1 for footnotes.

#### Attachment 4. Prop K and Prop AA Allocation Summaries - FY 2019/20

| PROP K SALES TAX      |    |            |    |            |    |              |    |             |    |           |    |           |    |           |    |         |
|-----------------------|----|------------|----|------------|----|--------------|----|-------------|----|-----------|----|-----------|----|-----------|----|---------|
|                       | To | tal        | Г  | Y 2019/20  | Б  | TY 2020/21   | Б  | FY 2021/22  | E  | Y 2022/23 | F  | Y 2023/24 | E  | Y 2024/25 | EV | 2025/26 |
| Prior Allocations     | \$ | 66,103,027 | \$ | 25,872,965 | -  | \$25,407,722 | 1  | \$6,032,974 | \$ | 2,690,622 | \$ | 2,690,622 | \$ | 2,690,622 | \$ | 717,500 |
| Current Request(s)    | \$ | 3,330,000  | \$ | 2,780,000  | \$ | 550,000      | \$ | -           | \$ | -         | \$ | -         | \$ | -         | \$ | -       |
| New Total Allocations | \$ | 69,433,027 | \$ | 28,652,965 | \$ | 25,957,722   | \$ | 6,032,974   | \$ | 2,690,622 | \$ | 2,690,622 | \$ | 2,690,622 | \$ | 717,500 |

The above table shows maximum annual cash flow for all FY 2019/20 allocations and appropriations approved to date, along with the current recommended allocation(s).



## San Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form

| FY of Allocation Action: | FY2019/20  |
|--------------------------|--|
| Project Name:            | Better Market Street - 5th to 8th Streets Design and Bikeway Pilot |
| Grant Recipient:         | Department of Public Works   |

#### **EXPENDITURE PLAN INFORMATION**

| Prop K EP categories:      | Guideways - Undesignated              |
|----------------------------|---------------------------------------|
| Current Prop K Request:    | \$3,330,000                           |
| Supervisorial District(s): | District 03, District 05, District 06 |

#### REQUEST

#### **Brief Project Description**

The Better Market Street project is comprised of various streetscape enhancements, transit capacity and reliability improvements, and state of good repair infrastructure along 2.2 miles of Market Street between Steuart Street and Octavia Boulevard. Key features include a new sidewalk-level cycle track and a F-Line loop to enable streetcars to turnaound in the mid-Market area. Requested funds are for detailed design from 5th to 8th streets, as well as installation and evaluation of a pilot sidewalk level bikeway along the south side of Market Street between Gough and Franklin streets.

#### Detailed Scope, Project Benefits and Community Outreach

#### Overall Project

Market Street is San Francisco's civic backbone, connecting water to hills, businesses to neighborhoods, cultural centers to recreational opportunities. The movement of people and goods, from the very earliest times, has dominated its design and use. Market Street is also San Francisco's most important transportation corridor, serving as the spine roadway within downtown San Francisco and linking the residential neighborhoods from the Twin Peaks foothills, through the Civic Center to the downtown Retail and Financial Districts.

Both the design of San Francisco's street network and its historic land use patterns have served to funnel movement, chiefly transit, to Market Street. Infrastructure investments in the 1970s and 1980s, first in the underground Bay Area Rapid Transit (BART) and Muni Metro systems, and then in the surface historic streetcar system, cemented Market Street's role as San Francisco's key transit corridor. Nearly one-third of Muni's all-day, weekday surface transit lines travel on Market Street. During the busiest hour of the day, over 100 buses and streetcars pass in each direction, transporting over 250,000 daily riders. Transit operational and on-time performance on Market Street impacts the entire Muni system – with delays and inefficiencies rippling out across San Francisco.

Market Street additionally is the Bay Area's most regionally significant rail corridor, providing underground Muni Metro light rail and BART regional rail service. The lower level BART service consists of six routes serving the San Francisco Bay Area with 420,000 average weekday daily passengers. Moreover, 2/3 of all BART trips begin or end at one of the four Market Street shared BART/Muni stations (Civic Center, Powell, Montgomery, and Embarcadero). The upper level consists of six Muni Metro light rail lines. Muni Metro is the United States' third-busiest light rail system, operating a fleet of 151 light rail vehicles (LRVs) with an average weekday ridership of 173,500 passengers.

Market Street is also San Francisco's busiest pedestrian thoroughfare, averaging 500,000 each day. Recently, Market Street also became the most popular route for bicyclists wishing to access downtown San Francisco, surpassing one million annual trips inbound to the Financial District for the first time in 2015, making it the busiest bicycling street west of the Mississippi. It is also part of San Francisco's High Injury Network developed to inform the city's efforts to achieve Vision Zero. In order to address the key challenges, five San Francisco City agencies have collaborated on a vision for a Better Market Street (BMS), which is a comprehensive program of projects to reconstruct 2.2 miles of the San Francisco's premier boulevard and most important transit corridor from Octavia Boulevard to The Embarcadero.

To accelerate project construction while providing time for funding to be secured for the overall project, the BMS program will be implemented in five phases. Phase 1A improvements will cover the portion of Market Street between 5th and 8th Streets and the logical tie-in points with existing infrastructure at each end. This work is located in the Central Market and Civic Center sections of Market Street. Central Market has been a neglected section of Market Street for over 50 years, and activating Central Market remains a priority.

The subject request includes \$2,230,000 to help complete funding for detailed design (currently at about 60%) of the segment along Market Street between 5th and 8th streets. Phase 1A work includes construction of sidewalk-level bicycle lanes, pavement renovation, utilities relocation and upgrades, and improvements on sidewalk; way-finding; lighting; landscaping; transit boarding islands; transit connections; and traffic signals.

SFPW, the SFMTA, PUC and OEWD will develop a Construction Mitigation Plan during the design phase. The project team will conduct outreach in order to collect input from businesses as they develop the plan. The Plan will include outreach during construction, and there will also be a project office for businesses to request support and services.

#### **Bikeway Pilot Implementation**

In Summer 2019 the project team conducted a Bikeway Separation Study to identify a separation material to install between the bikeway and pedestrian areas of the sidewalk. The material needed to be detectable by the blind and low vision; and it needed to be at least as easy to cross as truncated domes for people with mobility disabilities. The recommended material selected from the study, trapezoidal bar, would also help deter cyclists from riding on the sidewalk.

This request also includes \$1,100,000 to implement a pilot sidewalk level bikeway along the south side of Market Street between Gough and Franklin streets that will test the recommended bikeway separation material. The recommended separation material will be installed as a pilot program that will inform the design of this and future segments.

The pilot project will be implemented at the same site as a previous pilot which tested three different levels of raised bikeway at 2", 4" and 6" from the roadway. Results from the previous pilot project showed that the separation between bikeway and roadway is most effective at 6" since cars will still encroach the bikeway at 2" and 4". The results from that pilot were adopted by the Better Market Street project and are reflected in the proposed design of a sidewalk level bikeway.

Design of the pilot project has been completed (see attachment for design drawings) and is tentatively planned to be constructed between the beginning of March 2020 and the end of July 2020. The pilot project will construct a sidewalk level asphalt bikeway with detectable ADA separation material (trapezoidal bar) recommended by the project study conducted in Summer 2019. The pilot project will also reinstall granite curb, and install an asphalt sidewalk level bikeway and new pavers on the sidewalk as proposed for the Better Market Street project. The pilot project is located in the Better Market Street project segment between Octavia Boulevard and Van Ness Avenue, which is tentatively planned for construction no earlier than 2025. The pilot will run between July 2020 and December 2020. To evaluate the pilot, SFMTA and Public Works will conduct intercept surveys and bike and pedestrian counts.

#### **Project Location**

Market Street between 5th and 8th streets, Gough to Franklin

#### Project Phase(s)

Design Engineering (PS&E), Construction (CON)

#### Justification for Multi-phase Request

As part of the design phase of Phase 1A, Public Works is proposing implementation of a near-term improvement pilot to inform the design of this and future segments.

| 5YPP/STRATEGIC PLAN INFORMATION  |   |  |  |  |  |  |  |
|--|---|--|--|--|--|--|--|
| Type of Project in the Prop K 5YPP/Prop<br>AA Strategic Plan?                                  | Named Project                           |  |  |  |  |  |  |
| Is requested amount greater than the amount programmed in the relevant 5YPP or Strategic Plan? | Less than or Equal to Programmed Amount |  |  |  |  |  |  |
| Prop K 5YPP Amount:  | \$3,330,000                             |  |  |  |  |  |  |
|  |   |  |  |  |  |  |  |

## San Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form

| FY of Allocation Action: | FY2019/20  |
|--------------------------|--|
| Project Name:            | Better Market Street - 5th to 8th Streets Design and Bikeway Pilot |
| Grant Recipient:         | Department of Public Works   |

#### ENVIRONMENTAL CLEARANCE

Environmental Type: EIR/EIS

#### **PROJECT DELIVERY MILESTONES**

| Phase  | s           | Start         | End         |               |  |  |
|--|-------------|---------------|-------------|---------------|--|--|
|  | Quarter     | Calendar Year | Quarter     | Calendar Year |  |  |
| Planning/Conceptual Engineering                      | Oct-Nov-Dec | 2017          | Oct-Nov-Dec | 2018          |  |  |
| Environmental Studies (PA&ED)                        | Jul-Aug-Sep | 2015          | Jan-Feb-Mar | 2020          |  |  |
| Right of Way   |             |               |             |               |  |  |
| Design Engineering (PS&E)                            | Oct-Nov-Dec | 2018          | Apr-May-Jun | 2020          |  |  |
| Advertise Construction                               | Jul-Aug-Sep | 2020          |             |               |  |  |
| Start Construction (e.g. Award Contract)             | Oct-Nov-Dec | 2020          |             |               |  |  |
| Operations   |             |               |             |               |  |  |
| Open for Use   |             |               | Jan-Feb-Mar | 2023          |  |  |
| Project Completion (means last eligible expenditure) |             |               | Oct-Nov-Dec | 2021          |  |  |

#### SCHEDULE DETAILS

The schedule dates shown above are for Phase 1A of the Better Market Street project. In order to accelerate construction of the

project, SFPW has developed a strategy involving phased design and construction, where final design for later phases continues while earlier phases are under construction. SFPW will develop schedule milestones for construction of the remainder of the corridor as funding is secured.

#### Environmental Approval:

Planning Commission approved the CEQA Final Environmental Impacts Report on October 10, 2019. SFPW hosted a hearing on October 11, 2019 and adopted the project and findings in a Director's Order. The SFMTA Board has approved the legislation for the full corridor on October 15, 2019. The deadline to file an appeal related to CEQA was November 11 and no appeals were submitted. NEPA approval authority has been transferred to FHWA. Caltrans is in the process of reviewing the Environmental Assessment analysis and documents. SFPW anticpates NEPA approval by end of May 2020.

#### **Bikeway Pilot:**

Between the beginning of March 2020 and the end of July 2020, SFPW anticipates installing an asphalt sidewalk level bikeway, proposed ADA pavers and granite curb, and the trapezoidal bar detectable separation material recommended in the materials study conducted in Summer 2019. The pilot sidewalk level bikeway will be installed on Market Street between Gough and Franklin streets with the pilot anticipated to run from July 2020 to December 2020.

#### Public Engagement and Coordination with Other Projects.

Project team has been presenting the project and design alternative to various CAC and CBD and have hosted Open Houses in June and August 2019 for community outreach. Better Market Street project has been in coordination with Safer Taylor Street and 6th Street Improvement projects since all three projects are scheduled to be constructed in the same timeframe and are geographically close in proximity.

## San Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form

| FY of Allocation Action: | FY2019/20  |
|--------------------------|--|
| Project Name:            | Better Market Street - 5th to 8th Streets Design and Bikeway Pilot |
| Grant Recipient:         | Department of Public Works   |

#### FUNDING PLAN - FOR CURRENT REQUEST

| Fund Source                      | Planned | Programmed  | Allocated    | Project Total |
|----------------------------------|---------|-------------|--------------|---------------|
| PROP K: Guideways - Undesignated | \$0     | \$3,330,000 | \$0          | \$3,330,000   |
| BART MEASURE RR                  | \$0     | \$225,000   | \$0          | \$225,000     |
| PROP A GO BOND                   | \$0     | \$0         | \$11,545,000 | \$11,545,000  |
| PUC FUNDS (E.G. WW & WTR BOND)   | \$0     | \$3,500,000 | \$0          | \$3,500,000   |
| Phases in Current Request Total: | \$0     | \$7,055,000 | \$11,545,000 | \$18,600,000  |

#### FUNDING PLAN - ENTIRE PROJECT (ALL PHASES)

| Fund Source  | Planned      | Programmed    | Allocated    | Project Total |
|--|--------------|---------------|--------------|---------------|
| PROP K   | \$0          | \$13,864,000  | \$0          | \$13,864,000  |
| TBD (E.G. PROP A GO BOND, AHSC, SB1<br>LOCAL PARTNERSHIP PROGRAM<br>COMPETITIVE) | \$35,296,600 | \$0           | \$0          | \$35,296,600  |
| PUC FUNDS (E.G. WW & WTR BOND)   | \$36,500,000 | \$3,500,000   | \$0          | \$40,000,000  |
| PROP A GO BOND   | \$0          | \$75,653,000  | \$24,623,000 | \$100,276,000 |
| OCTAVIA LAND SALES   | \$0          | \$0           | \$3,050,000  | \$3,050,000   |
| OBAG 2   | \$0          | \$3,366,000   | \$0          | \$3,366,000   |
| MTA OPERATING REVENUE  | \$0          | \$0           | \$3,000,000  | \$3,000,000   |
| MARKET OCTAVIA IMPACT FEES   | \$0          | \$0           | \$1,000,000  | \$1,000,000   |
| GENERAL FUND   | \$0          | \$0           | \$5,100,000  | \$5,100,000   |
| BUILD (FEDERAL)  | \$0          | \$15,000,000  | \$0          | \$15,000,000  |
| BART MEASURE RR  | \$0          | \$635,000     | \$0          | \$635,000     |
| Funding Plan for Entire Project Total:   | \$71,796,600 | \$112,018,000 | \$36,773,000 | \$220,587,600 |

#### **COST SUMMARY**

| Phase                           | Total Cost    | Prop K -<br>Current<br>Request | Source of Cost Estimate                 |  |  |  |  |
|---------------------------------|---------------|--------------------------------|---|--|--|--|--|
| Planning/Conceptual Engineering | \$15,754,000  | \$0                            | Actuals                                 |  |  |  |  |
| Environmental Studies (PA&ED)   | \$9,474,000   | \$0                            | Actuals and Cost to Complete            |  |  |  |  |
| Right of Way                    | \$0           | \$0                            |   |  |  |  |  |
| Design Engineering (PS&E)       | \$17,500,000  | \$2,230,000                    | 10% of Construction Cost                |  |  |  |  |
| Construction (CON)              | \$177,859,600 | \$1,100,000                    | Engineer's estimate (\$1.1 m for Pilot) |  |  |  |  |
| Operations                      | \$0           | \$0                            |   |  |  |  |  |
| Total:                          | \$220,587,600 | \$3,330,000                    |   |  |  |  |  |
| % Complete of Design: 60.0%     |               |                                |   |  |  |  |  |

| % Complete of Design: | 60.0%      |
|-----------------------|------------|
| As of Date:           | 09/10/2019 |
| Expected Useful Life: | 50 Years   |

#### MAJOR LINE ITEM BUDGET

| SUMMARY BY MAJOR LINE ITEM - DESIGN |                     |            |  |  |  |  |  |
|-------------------------------------|---------------------|------------|--|--|--|--|--|
| Budget Line Item                    | n Totals % of phase |            |  |  |  |  |  |
| 1. Total Labor                      | \$                  | 17,500,000 |  |  |  |  |  |
| 2. Consultant                       |                     |            |  |  |  |  |  |
| 3. Other Direct Costs *             |                     |            |  |  |  |  |  |
| 4. Contingency                      |                     |            |  |  |  |  |  |
| TOTAL PHASE                         | \$                  | 17,500,000 |  |  |  |  |  |

| TOTAL LABOR COST BY AGENCY | TOTAL | LABOR | COST BY | AGENCY |
|----------------------------|-------|-------|---------|--------|
|----------------------------|-------|-------|---------|--------|

| SFMTA | \$<br>7,000,000  |
|-------|------------------|
| SFPW  | \$<br>10,500,000 |
| TOTAL | \$<br>17,500,000 |

#### MAJOR LINE ITEM BUDGET

| SUMMARY BY MAJOR LINE I     | TEM ( | BY AGENCY | LABOR BY TASK | )  |         |       |   |    |          |
|-----------------------------|-------|-----------|---------------|----|---------|-------|---|----|----------|
| Budget Line Item            |       | Totals    | % of contract |    | SFPW    | SFMTA |   | Со | ntractor |
| Roadway Work                | \$    | 111,000   |               |    |         |       |   | \$ | 111,000  |
| Landscape Work*             | \$    | 468,000   |               |    |         |       |   | \$ | 468,000  |
| Subtotal                    | \$    | 579,000   |               |    |         |       |   | \$ | 579,000  |
|                             |       |           |               |    |         |       |   |    |          |
| Traffic Routing             | \$    | 174,000   | 30%           |    |         |       |   | \$ | 174,000  |
| Mobilization                | \$    | 46,320    | 8%            |    |         |       |   | \$ | 46,320   |
| Demobilization              | \$    | 28,950    | 5%            |    |         |       |   | \$ | 28,950   |
| Subtotal                    | \$    | 828,270   |               |    |         |       |   | \$ | 828,270  |
| Construction Contingency    | \$    | 82,827    | 10%           | \$ | 82,827  |       |   |    |          |
| Total Construction Estimate | \$    | 911,097   |               |    |         |       |   |    |          |
|                             |       |           |               |    |         |       |   |    |          |
| Construction Support        | \$    | 188,903   | 21%           | \$ | 188,903 |       |   |    |          |
| TOTAL PILOT                 | \$    | 1,100,000 |               | \$ | 271,730 | \$    | - | \$ | 828,270  |

\*Landscape Work includes all of the sidewalk work including granite curbs, pavers, and the bikeway separation.

## San Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form

| FY of Allocation Action: | FY2019/20  |
|--------------------------|--|
| Project Name:            | Better Market Street - 5th to 8th Streets Design and Bikeway Pilot |
| Grant Recipient:         | Department of Public Works   |

#### SFCTA RECOMMENDATION

|     | Resolution Date:           |             | Resolution Number:        |
|-----|----------------------------|-------------|---------------------------|
| \$0 | Total Prop AA Requested:   | \$3,330,000 | Total Prop K Requested:   |
| \$0 | Total Prop AA Recommended: | \$3,330,000 | Total Prop K Recommended: |

| SGA Project Number:                            |                            |            |            | Name:      | Bette      | er Market Street | - Bikeway Pilot |
|--|----------------------------|------------|------------|------------|------------|------------------|-----------------|
| Sponsor:                                       | Department of Public Works |            | Expira     | tion Date: | 03/31/2024 |                  |                 |
| Phase:   | Construction               |            | F          | undshare:  | 17.9       |                  |                 |
| Cash Flow Distribution Schedule by Fiscal Year |                            |            |            |            |            |                  |                 |
| Fund Source                                    | FY 2019/20                 | FY 2020/21 | FY 2021/22 | FY 2022/23 |            | FY 2023/24       | Total           |
| PROP K EP-120U                                 | \$550,000                  | \$550,000  | \$0        | \$0        |            | \$0              | \$1,100,000     |
|  |                            |            |            |            |            |                  |                 |

#### Deliverables

1. The first quarterly progress report shall include 2-3 photos of typical before conditions and data on the before conditions to support the pilot evaluation, in addition to all other requirements described in the Standard Grant Agreement (SGA). Over the course of the project, quarterly progress reports should include 2-3 photos of the bikeway pilot under construction and in use. See SGA for definitions.

2. With the progress report and quarterly project update to the Transportation Authority Board in Fall 2020, SFPW will provide preliminary results for the Bikeway pilot evaluation.

3. Upon completion, SFPW will provide an electronic copy of the results of the Bikeway Pilot evaluation.

#### **Special Conditions**

1. The recommended allocation is contingent upon SFPW's continued compliance with quarterly project reporting on the Better Market Street project to the Transportation Authority Board, established as a condition of receiving OBAG funding.

| SGA Project Number: |  |                    |         |            | Name:      |      | er Market Street<br>ets Design | - 5th to 8th |
|---------------------|--|--------------------|---------|------------|------------|------|--------------------------------|--------------|
| Sponsor:            | Department of Public Works                     |                    | Expirat | tion Date: | 12/31/2020 |      |                                |              |
| Phase:              | Design Engine                                  | Design Engineering |         | Fu         | undshare:  | 17.9 |                                |              |
|                     | Cash Flow Distribution Schedule by Fiscal Year |                    |         |            |            |      |                                |              |
| Fund Source         | FY 2019/20                                     | FY 2020/21         | FY      | 2021/22    | FY 2022/   | 23   | FY 2023/24                     | Total        |
| PROP K EP-120U      | \$2,230,000                                    | \$0                |         | \$0        |            | \$0  | \$0                            | \$2,230,000  |

#### Deliverables

1. With the first quarterly progress report due January 15, 2020, provide 2-3 photos of typical before conditions.

2. Upon project completion, provide evidence of completion of 100% design (e.g. copy of certifications page).

3. Upon completion, provide an updated scope, schedule, budget and funding plan for construction of Phase 1A (5th to 8th streets). This can be satisfied by submitting an allocation request for construction.

#### **Special Conditions**

1. The recommended allocation is contingent upon SFPW's continued compliance with quarterly project reporting on the Better Market Street project to the Transportation Authority Board, established as a condition of receiving OBAG funding.

| Metric                              | Prop K | Prop AA    |
|-------------------------------------|--------|------------|
| Actual Leveraging - Current Request | 82.1%  | No Prop AA |
| Actual Leveraging - This Project    | 93.71% | No Prop AA |

## San Francisco County Transportation Authority Prop K/Prop AA Allocation Request Form

| FY of Allocation Action: | FY2019/20  |
|--------------------------|--|
| Project Name:            | Better Market Street - 5th to 8th Streets Design and Bikeway Pilot |
| Grant Recipient:         | Department of Public Works   |

#### **EXPENDITURE PLAN INFORMATION**

1) The requested sales tax and/or vehicle registration fee revenues will be used to supplement and under no circumstance replace existing local revenues used for transportation purposes.

Initials of sponsor staff member verifying the above statement


OQ

#### **CONTACT INFORMATION**

|        | Project Manager           | Grants Manager              |
|--------|---------------------------|-----------------------------|
| Name:  | Cristina Olea (SFDPW)     | Oscar Quintanilla           |
| Title: | Project Manager           | Capital Budget Analyst      |
| Phone: | (415) 558-4004            | (415) 554-5847              |
| Email: | cristina.c.olea@sfdpw.org | oscar.quintanilla@sfdpw.org |

#### Attachment 2: Project Component Cost Breakdown

Based on 10% design



\$604M Cost Estimate

#### Better Market Street Funding Plan All Dollars in Thousands

#### SECURED FUNDING

| Funding Source                             | Status     | Full Corridor Env. | Design | Construction | Future Phases | Total by Fund |
|--|------------|--------------------|--------|--------------|---------------|---------------|
|  |            | Review & 30%       | Ph. 1A | Ph. 1A       |               | Source        |
|  |            | Design             |        |              |               |               |
| General Fund                               | Allocated  | 5,100              |        |              |               | 5,100         |
| Octavia Land Sales                         | Allocated  | 3,050              |        |              |               | 3,050         |
| Market Octavia Impact Fees                 | Allocated  | 1,000              |        |              |               | 1,000         |
| Transit Center Impact Fees                 | Allocated  |                    |        |              | 2,000         | 2,000         |
| Prop A GO Bond                             | Allocated  | 13,078             | 11,545 |              |               | 24,623        |
| MTA Operating Funds                        | Allocated  | 3,000              |        |              |               | 3,000         |
| Prop A GO Bond                             | Programmed |                    |        | 72,123       |               | 72,123        |
| BART (8th/Grove/Hyde/Market)               | Programmed |                    | 225    | 410          |               | 635           |
| OBAG                                       | Programmed |                    |        | 3,366        |               | 3,366         |
| Prop K (EP 22 & 44)                        | Programmed |                    | 2,230  | 11,634       |               | 13,864        |
| BUILD                                      | Programmed |                    |        | 15,000       |               | 15,000        |
| PUC Sewer and Water Funds                  | Planned    |                    | 3,500  |              |               | 3,500         |
| PUC Sewer and Water Funds                  | Planned    |                    |        | 36,500       |               | 36,500        |
| TBD (e.g. MTA Bond, AHSC, LPP Competitive) | Planned    |                    |        | 38,826       |               | 38,826        |
| Total Identified Funding by Phase          |            | 25,228             | 17,500 | 177,859      | 2,000         | 222,587       |

#### OTHER POTENTIAL FUNDING SOURCES

| officient of citrate i on bind so onces            | -       |                    |        |              |               |               |
|--|---------|--------------------|--------|--------------|---------------|---------------|
| Funding Source                                     | Status  | Full Corridor Env. | Design | Construction | Future Phases | Total by Fund |
|  |         | Review & 30%       | Ph. 1A | Ph. 1A       |               | Source        |
|  |         | Design             |        |              |               |               |
| FTA 5309 (New Starts, Small Starts, Core Capacity) | Planned |                    |        |              |               |               |
| FTA 5337 Fixed Guideway                            | Planned |                    |        |              |               |               |
| BUILD  | Planned |                    |        |              |               |               |
| OBAG 3 (FYs 2022/23-2026/27)                       | Planned |                    |        |              |               |               |
| Senate Bill (SB) 1                                 | Planned |                    |        |              |               |               |
| Cap & Trade  | Planned |                    |        |              |               |               |
| Active Transportation Program (ATP)                | Planned |                    |        |              |               |               |
| Local Partnership Program (LPP)                    | Planned |                    |        |              |               |               |
| Regional Measure 3 (bridge tolls): Phase 1         | Planned |                    |        |              | 4,872         |               |
| Regional Measure 3 (bridge tolls)                  | Planned |                    |        |              | 20,128        |               |
| Ргор К   | Planned |                    |        |              |               |               |
| Transit Center Impact Fees                         | Planned |                    |        |              |               |               |
| MTA Prop B General Fund set-aside                  | Planned |                    |        |              |               |               |
| TNC Tax  | Planned |                    |        |              |               |               |
| Vehicle License Fee                                | Planned |                    |        |              |               |               |
| Bonds  | Planned |                    |        |              |               |               |

#### Better Market Street

Project Schedule

| Commont            | Dhase        | Schedule, by Fiscal Year |          |          |          |          |          |          |          |          |
|--------------------|--------------|--------------------------|----------|----------|----------|----------|----------|----------|----------|----------|
| Segment            | Phase        | FY 18/19                 | FY 19/20 | FY 20/21 | FY 21/22 | FY 22/23 | FY 23/24 | FY 24/25 | FY 25/26 | FY 26/27 |
| Phase 1a - 5th-8th | Design       | Х                        | Х        |          |          |          |          |          |          |          |
| Phase 1a - 5th-8th | Construction |                          |          | Х        | Х        |          |          |          |          |          |
| Phase 1b - F Loop  | Design       |                          | Х        | Х        |          |          |          |          |          |          |
| Phase 1b - F Loop  | Construction |                          |          |          | Х        | Х        |          |          |          |          |
| Segment 2          | Design       |                          |          | Х        | Х        |          |          |          |          |          |
| Segment 2          | Construction |                          |          |          |          | Х        | Х        |          |          |          |
| Segment 3          | Design       |                          |          |          |          | Х        |          |          |          |          |
| Segment 3          | Construction |                          |          |          |          |          | Х        | Х        |          |          |
| Segment 4          | Design       |                          |          |          |          |          | Х        |          |          |          |
| Segment 4          | Construction |                          |          |          |          |          |          | Х        | Х        |          |
| Segment 5          | Design       |                          |          |          |          |          |          | Х        |          |          |
| Segment 5          | Construction |                          |          |          |          |          |          |          | Х        | Х        |


Possible Segments: Steuart St - 2nd St 2nd St - 5th St 8th St - 12th St 12th St - Octavia Boulevard

# 於馬 PAVING & ACCESSIBILITY



# Better Market Street proposes new sidewalk paving that is accessible, durable and easily maintained.


Sidewalk use zones will be delineated using variations in paving materials and the scale, proportion and color of those materials. The design of paving patterns will result in an urban design that is memorable and unique to Market Street and to San Francisco.






A Pedestrian Realm Focus Group working with the project team and the Mayor's Office on Disability, evaluated the sidewalk paving on Market Street. The resulting report recommended replacing the brick on Market Street with a safe, durable and smooth paver. And in 2018, San Francisco adopted a paving standard for city sidewalks that requires concrete pavers to have joints at least 18" apart. A delineation zone between the pedestrian walkway and bikeway is recommended. A pilot is underway to develop a standard for this feature.

## Potential Path Delineator







Market Street has uniquely oblique intersections. The sidewalk paving design will highlight this characteristic through paving color and texture.



The project intends to reuse the existing granite curbs throughout the street, either as curbs or site furnishings.




15 of 25



FRONTAGE AND STREETLIFE **SIDEWALK** CURBSIDE SHARED LANE **MUNI-ONLY MUNI-ONLY** CENTER SHARED LANE SIDEWALK STREETLIFE FRONTAGE AND PEDESTRIAN ZONE LEVEL TRANSIT LANE LANE TRANSIT LEVEL ZONE PEDESTRIAN THROUGH ZONE BIKEWAY STOP BOARDING BIKEWAY THROUGH ZONE








## **Rapid Center Lane Service:**

Stops located only at BART/Muni Metro stations would provide easy transfers and faster service. Transit customers would have to walk no more than two blocks to access the closest center-lane stop.



The proposed extension of the red Muni-Only lanes will keep transit moving, even during busy times on Market Street.

The project is expected to provide up to 25% travel time savings by changing stop spacing, reducing conflicts with bikes, and extending Muni-only lanes.

Maintain Curbside Local Service: Curbside stops would remain at about every block and Civic Center would serve as a convenient transfer point for those wanting to minimize walking.



conflicts with people biking.



The proposed sidewalk-level bikeway will help speed up transit by reducing




# SITE FURNISHINGS: SEATING




The furnishing zones on Market Street's sidewalks also provide the opportunity for seating, allowing people to socialize and linger. In keeping with the project's goal of sustainability, the existing Sierra White Granite curbs could be refashioned into seating elements. Alternatively, seating could be made from locally sourced or reclaimed lumber.



A 20 foot long furnishing zone can be designed and programmed to accommodate different amenities and uses to provide comfort and engagement along Market Street. The zone width varies from 4 to 10 feet.



SEATING LAYOUT There are numerous ways that seating elements could be arranged within the furnishing zone.



## SEATING STYLE AND MATERIALS















17 of 25




# SITE FURNISHINGS


# BETTER MARKET STREET

18 of 25


# The furnishing zone on Market Street needs to accommodate many uses and elements, not just seating. Today, the above-ground elements give the street a haphazard and cluttered appearance. Better Market Street will streamline the site furnishings as much as possible.

SITE FURNISHINGS TO COORDINATE: Kiosks, restrooms and BART portals





A 20 foot long furnishing zone can be designed and programmed to accommodate different amenities and uses to provide comfort and engagement along Market Street. The zone width varies from 4 to 10 feet.



## SITE FURNISHINGS TO ACCOMMODATE:


Railings, bus shelters, lights, bike racks and bike amenities



## Bike share, newsracks, advertising panels and trash cans








## Landmarks













TAX








one letter and six numbers






## SIDEWALK-LEVEL BIKEWAY PILOT FOR BETTER MARKET STREET PROJECT CONTRACT NO. 2752J

City and County of San Francisco London Breed, Mayor Mohammed Nuru, Director



LOCATION




| REFERENCE INFORMATION & FILE NO. OF SURVEYS  | AND COUNTY OF SA                         | SAN FRANCISCO                     | Date: Acting Section Mgr: ERIC KJELSBERG Deputy Bureau Mgr: FERNANDO CISNEROS | DESIGNED: DATE:<br>J. MUNOZ 09/19<br>DRAWN: DATE: | SCALE:<br>NONE        |  |
|--|--|-----------------------------------|---|---|-----------------------|--|
| NO.         DATE         DESCRIPTION         BY         APP.           TABLE OF REVISIONS         TABLE OF REVISIONS         THIS DRAWING WAS LAST MODIFIED: 09/11/19 11:31, BY: jmunoz         jmunoz | 10 10 10 10 10 10 10 10 10 10 10 10 10 1 | PUBLIC SAN FRANCISCO PUBLIC WORKS | Bureau Mgr: PATRICK RIVERA  | J. MUNOZ 09/19<br>CHECKED: DATE:<br>C. YU 09/19   | SHEET OF SHEETS<br>OF |  |

| MAP  | City Engineer                                | Xrefs: \\dpw.ci.sf.co.us\boe\BOEFILES1\Data\  |
|--|--|---|
|  |  | Diawing Path: Si/SH\Josef\Sidewalk-Level Bikeway Pilot\Plans\BMS Rajeed Cycletrack Transition Analysis_CoverPage.dbgnbeogen Bioanter21<br>Diawing Path: Si/SH\Josef\Sidewalk-Level Bikeway Pilot\Plans\BMS Rajeed Cycletrack Transition Analysis_CoverPage.dbgnbeogen Bioanter21<br>Diawing Path: Since 2010 111.0000 |
| SIDEWALK-LEVEL BIKEWAY PILOT<br>FOR BETTER MARKET STREET | contract no.<br>2752J<br>drawing no.<br>R-GO | SH\Josef\Sidewa   |
| COVER PAGE   | FILE NO.                                     | Irawing Path: S:\   |
|  |  |   |

Public Works Design and Construction

> John F. Thomas, P.E. City Engineer





| DWG       REV       FILE       DRAWING TITLE         GENERAL         G-G0       COVER PAGE         G-G1       VICINITY MAP & INDEX OF DRAWINGS         G-G2       LEGEND AND ABBREVIATIONS         G-G3       GENERAL NOTES         ROADWAY DETAILS         R-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN DET         R-2       MARKET ST FROM BRADY TO FRANKLIN ST DESIGN DET         L-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN         L-2       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN |      |  |  |
|---|------|--|--|
| G-G0       COVER PAGE         G-G1       VICINITY MAP & INDEX OF DRAWINGS         G-G2       LEGEND AND ABBREVIATIONS         G-G3       GENERAL NOTES         ROADWAY DETAILS         R-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN DET         LANDSCAPE         L-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN  |      |  | DRAWING TITLE                                  |
| G-G1       VICINITY MAP & INDEX OF DRAWINGS         G-G2       LEGEND AND ABBREVIATIONS         G-G3       GENERAL NOTES         ROADWAY DETAILS         R-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN DE         R-2       MARKET ST FROM BRADY TO FRANKLIN ST DESIGN DET         LANDSCAPE         L-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN  |      |  | GENERAL  |
| G-G2       LEGEND AND ABBREVIATIONS         G-G3       GENERAL NOTES         ROADWAY DETAILS         R-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN DE         R-2       MARKET ST FROM BRADY TO FRANKLIN ST DESIGN DET         LANDSCAPE         L-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN  | G-GO |  | COVER PAGE                                     |
| G-G3       GENERAL NOTES         ROADWAY DETAILS         R-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN DE         R-2       MARKET ST FROM BRADY TO FRANKLIN ST DESIGN DET         LANDSCAPE         L-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN  | G-G1 |  | VICINITY MAP & INDEX OF DRAWINGS               |
| ROADWAY DETAILS         R-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN DET         R-2       MARKET ST FROM BRADY TO FRANKLIN ST DESIGN DET         LANDSCAPE         L-1       MARKET ST FROM GOUGH ST TO BRADY ST DESIGN  | G-G2 |  | LEGEND AND ABBREVIATIONS                       |
| R-1     MARKET ST FROM GOUGH ST TO BRADY ST DESIGN DE       R-2     MARKET ST FROM BRADY TO FRANKLIN ST DESIGN DET       LANDSCAPE       L-1     MARKET ST FROM GOUGH ST TO BRADY ST DESIGN   | G-G3 |  | GENERAL NOTES                                  |
| R-2     MARKET ST FROM BRADY TO FRANKLIN ST DESIGN DET       LANDSCAPE       L-1     MARKET ST FROM GOUGH ST TO BRADY ST DESIGN   |      |  | ROADWAY DETAILS                                |
| LANDSCAPE L-1 MARKET ST FROM GOUGH ST TO BRADY ST DESIGN  | R-1  |  | MARKET ST FROM GOUGH ST TO BRADY ST DESIGN DE  |
| L-1 MARKET ST FROM GOUGH ST TO BRADY ST DESIGN  | R-2  |  | MARKET ST FROM BRADY TO FRANKLIN ST DESIGN DET |
|   |      |  | LANDSCAPE                                      |
| L-2 MARKET ST FROM GOUGH ST TO BRADY ST DESIGN  | L-1  |  | MARKET ST FROM GOUGH ST TO BRADY ST DESIGN     |
|   | L-2  |  | MARKET ST FROM GOUGH ST TO BRADY ST DESIGN     |

|  | NO. DATE DESCRIPTION BY APP.<br>TABLE OF REVISIONS<br>THIS DRAWING WAS LAST MODIFIED: 09/11/19 13:14, BY: jmunoz | REFERENCE INFORMATION & FILE NO. OF SURVEYS | Dir son FR | SAN FRANCISCO<br>PUBLIC<br>WORKS<br>BUREAU OF<br>ENGINEERING<br>OTY & COUNTY OF SAN F<br>SAN FRANCISCO P<br>30 VAN NESS AVENUE, ST<br>SAN FRANCISCO, CA 9410 | NCISCO Deputy Bureau Mgr: FERNANDO CISNEROS<br>BLIC WORKS<br>FLOOR Bureau Mgr: PATRICK RIVERA | J. MUNOZ (<br>DRAWN: D<br>J. MUNOZ (<br>CHECKED: D | ATE: | SCALE:<br>NONE<br>SHEET OF SHEETS<br>OF |  |
|--|--|---|------------|--|---|--|------|---|--|
|--|--|---|------------|--|---|--|------|---|--|

| TAIL AND CROSS SECTION<br>AIL AND CROSS SECTION<br>AIL AND CROSS SECTION |  | Drawing Ptdr: S/S/NJoseY/Sidewalk-Level Bikeway Pilot/Plans/BMS Raised Cycletrack Transition Analysis_CoverPage.dm2jmebmez1 2013.dmg<br>Plot Time: Wed, 11 Sep 2019 – 1:17pm Weasurement Units are English Model Units: Feet |
|--|--|--|
| SIDEWALK-LEVEL BIKEWAY PILOT<br>FOR BETTER MARKET STREET                 | contract no.<br>2752J<br>drawing no.<br>R-G1<br>file no. | S:\SH\Josef\S<br>11 Sep 2019   |
| VICINITY MAP AND INDEX OF DRAWINGS                                       | REV. NO.   | Drawing Path:<br>Plot Time: Wec  |

|                         | LEGEND  | )   | _                               |              |                                  |             | ABBREV                           | ATIONS        | 5                                  |
|-------------------------|---|---|---------------------------------|--------------|----------------------------------|-------------|----------------------------------|---------------|------------------------------------|
|                         | APPROXIMATE AREA TO BE COLD PLANED 2-INCH FULL DEPTH OF CUT   | FIG   | TOP OF CURB OR SIDEWALK O       |              |                                  | AB          | ASSESSOR'S BLOCK                 | LE            | LINE END                           |
|                         | AND RESTORED WITH 2–INCH THICK MINIMUM OF ACWS. EXACT LOCATION<br>AND DIMENSIONS TO BE DETERMINED BY THE CITY REPRESENTATIVE IN THE FIELD   | FIG   | FLOW LINE/GUTTER OR CATCH       |              |                                  | AC          | ASPHALT CONCRETE                 | LPFH          | LOW PRESSURE HIGH HYDRANT          |
|                         |   | /   | /                               |              |                                  | ACWS        | ASPHALT CONCRETE WEARING SURFACE | L1            | LINE 1, ETC                        |
|                         | APPROXIMATE AREA TO BE RECONSTRUCTED WITH 2-INCH THICK<br>MINIMUM OF ACWS ON 8-INCH THICK CONCRETE BASE. EXACT LOCATION   | FIGxFIG   | APPROXIMATE DIMENSIONS, IN      | FEET, OF CON | CRETE BASE RECONSTRUCTION        | AWSS        | AUXILIARY WATER SUPPLY SYSTEM    | MAX           | MAXIMUM                            |
|                         | AND DIMENSIONS TO BE DETERMINED BY THE CITY REPRESENTATIVE IN THE FIELD   |   |                                 |              |                                  | BC          | CURVE BEGINNING                  | MIN           | MINIMUM                            |
|                         |   | FIG   | Section/Detail Indentificatio   | N            |                                  | BLDG        | BUILDING                         | MFN           | METROMEDIA FIBER OPTIC CABLE NETWO |
|                         | 12-INCH WIDE TRAPEZOIDAL DELINEATOR   | FIG.  | DRAWING NO.                     | <u></u>      |                                  | BLHP        | BUREAU OF LIGHT, HEAT AND POWER  | МН            | MANHOLE                            |
|                         |   | I   |                                 |              |                                  | BOT         | воттом                           | MTR           | METER                              |
| ┠╺╌┙┍┙┍┙┍┙┍ <b>┙</b> ┍┚ |   | 0   | AWNING POLE                     | Ø            | HOSE BIB                         | BRK         | GRADE BREAK                      | MON           | MONUMENT                           |
|                         | INSTALL PRECAST CONCRETE GRANITE FINISH CURB  |   |                                 |              |                                  | BSW         | BACK OF SIDEWALK                 | (N)           | NEW                                |
|                         |   | ÷   | BENCH MARK                      | -Ò-          | LIGHT POLE                       | BVC         | VERTICAL TANGENT-CURVE INTERSECT | N/A           | NOT APPLICABLE                     |
|                         | CONSTRUCT 6-INCH OR 14-INCH WIDE CONCRETE HEADER  |   |                                 | × 1 ×        |                                  | С           | CURB                             | NO.           | NUMBER                             |
|                         | CONSTRUCT OF INCH OR 14-INCH WIDE CONCRETE HEADER   | M   | BIKE RACK                       | $\bigcirc$   | MUNI GUY POLE                    | СВ          | CATCH BASIN                      | NIC           | NOT IN CONTRACT                    |
|                         | APPROXIMATE LIMITS OF EXISTING BASEMENT BENEATH THE SIDEWALK, CURB, AND/OR  |   |                                 | <u> </u>     |                                  | CL          | CENTER LINE                      | NTS           | NOT TO SCALE                       |
|                         | APPROXIMATE LIMITS OF EXISTING BASEMENT BENEATH THE SIDEWALL, CURE, AND/OR<br>ROADWAY. PRIOR TO ANY WORK THE CONTRACTOR SHALL VERIFY BASEMENT LIMITS<br>AND NOTIFY THE CITY REPRESENTATIVE IN WRITING ANY CONFLICTS | ٠   | BOLLARD -                       |              | MUNI GUY POLE WITH LIGHT         | со          | SANITARY SEWER CLEANOUT/VENT     | OCS           | OVERHEAD CONTACT SYSTEM            |
|                         | AND NOTET THE OTT REFRESENTATIVE IN WRITING ANY CONFLICTS   | -   | 个`                              |              |                                  | СОММ        | COMMUNICATIONS                   | OG            | OUTSIDE GUTTER                     |
|                         |   |   | (N) CATCH BASIN                 |              | USPS MAIL BOX                    | CONC        | CONCRETE                         | PB            | PULL BOX                           |
|                         | EXISTING MUNI OVERHEAD CONTACT SYSTEM (OCS) WIRES   |   |                                 | 4            |                                  | CR          | CURB RAMP                        | PC            | POINT OF CURVATURE/                |
|                         |   |   | (E) CATCH BASIN TO REMAIN       | RELAY        | USPS MAIL BOX RELAY              | C1          | CURVE 1, ETC                     |               | TANGENT-CURVE INTERSECT            |
|                         | EXISTING CURB/GUTTER/PARKING STRIP/ISLAND   | متلالاللك                                       |                                 | RELAY        |                                  | DT          | DEPARTMENT OF TECHNOLOGY         | PCC           | POINT OF HORIZONTAL COMPOUND CUR   |
|                         | EXISTING CONDY GUTTERY FARMING STRIFY ISLAND  | $\square$                                       | (E) CATCH BASIN TO BE ABANDONED | $\bigotimes$ | PARKING METER                    | DWG         | DRAWING                          |               | COMPOUND CURVE-CURVE INTERSECT     |
|                         |   |   |                                 |              |                                  | DWY         | DRIVEWAY                         | PI            | POINT OF INTERSECTION/             |
|                         | APPROXIMATE LOCATION OF PROPERTY LINE   |   | CITY MONUMENT                   | 8            | SEWER CLEAN OUT                  | (E), EX     | EXISTING                         |               | TANGENT-TANGENT INTERSECT          |
|                         | CONFORM LINE  |   |                                 |              |                                  | EA          | EACH                             | PL            | PROPERTY LINE                      |
|                         |   | 0   | CONDUIT                         | <u> </u>     | SIGN POLE(S)                     | EC          | CURVE END                        | PRC           | POINT OF HORIZONTAL REVERSE CURVE  |
|                         | MATCH LINE  |   |                                 | <b></b> 0    |                                  | EL, ELEV    | ELEVATION                        |               | REVERSE CURVE-CURVE INTERSECT      |
|                         |   | _ <b>&gt;</b>                                   | DIRECTION OF DRAINAGE FLOW      | 63           | SPRINKLER                        | ENT         | ENTRANCE                         | PT            | POINT OF TANGENCY/                 |
|                         |   |   |                                 | <b>1</b>     |                                  | EQ          | EQUAL                            |               | CURVE-TANGENT INTERSECT            |
|                         |   | Q   | DOWN SPOUT                      | 8            | STAND PIPE                       | EVC         | VERTICAL CURVE-TANGENT INTERSECT | PVI           | POINT OF VERTICAL INTERSECTION     |
|                         |   |   |                                 | 0            |                                  | FA          | FIRE ALARM POLE                  | REF PT        | REFERENCE POINT                    |
|                         |   | <b>\$</b>                                       | ELECTROLIER                     | $\wedge$     | SURVEY CONTROL POINT             | FH          | FIRE HYDRANT                     | REV           | REVISION                           |
|                         |   | 710   |                                 |              |                                  | FIG         | FIGURE                           | ROW           | RIGHT-OF-WAY                       |
|                         |   | +0+   | FIRE HYDRANT                    | $\cap$       | TRAFFIC SIGNAL                   | FL          | FLOW LINE                        | S, SW         | SEWER                              |
|                         |   |   |                                 | 2            | HALLO SIGNAL                     | G           | GUTTER                           | SWLK          | SIDEWALK                           |
|                         |   | Ę   | FIRE HYDRANT VALVE              | <u>ANK</u>   | UNKNOWN VALVE                    | GB          | GRADE BREAK                      | SL            | STREET LIGHTING                    |
|                         |   |   |                                 |              |                                  | GR          | GRATE                            | STA           | STATION                            |
|                         |   | ŧ   | GAS VALVE                       | œ            | WATER VALVE                      | GV          | GAS VALVE                        | TS            | TRAFFIC SIGNAL                     |
|                         |   | *   |                                 | - markanan   | 17731EIX 774EYE                  | HYD         | HYDRANT                          | TW            | TOP OF WALL                        |
|                         |   | 4©+   | HPFS HYDRANT                    | for the      | TREE                             | HP          | HIGH POINT                       | TYP           | TYPICAL                            |
|                         |   |   |                                 |              | INLL                             | HPFH        | HIGH PRESSURE FIRE HYDRANT       | UNK           | UNKNOWN                            |
|                         |   | ı)ı   | HPFS VALVE                      | · #45-14     |                                  | HPFS        | HIGH PRESSURE FIRE SERVICE       | USPS          | UNITED STATES POSTAL SERVICE       |
|                         |   |   |                                 |              |                                  | IRV         | IRRIGATION VALVE                 | UTIL          | UTILITY                            |
|                         | 95% RE  | VIEW  |                                 |              |                                  | LB          | LINE BEGINNING                   | WM            | WATER METER                        |
|                         | NOT FOR CON   | STRUCTION                                       |                                 |              |                                  | 20          |                                  | WV            | WATER VALVE                        |
|                         | REFERENCE INFORMATION<br>& FILE NO. OF SURVEYS  |   |                                 | Date:        | DESIGNED: DATE:                  | SCALE:      |                                  | יייריצורים וק | CONTRACT NO.                       |
|                         | & FILE NO. OF SURVEYS   | BUREAU OF<br>ENGINEERING                        | Acting Section Mgr: ERIC KJE    | ELSBERG      | J. MUNOZ 09/19                   | NON         | E SIDEWALK-LEV<br>FOR BETTER     |               | STREFT DRAWING NO.                 |
|                         | SAN FRANCISCO   | CITY & COUNTY OF SAN FRAM                       |                                 | ISNEROS      | DRAWN: DATE:                     |             | FOR BETTER                       | MAINTEL       | R-G2                               |
| DESCRIPTION             | BY APP.   | SAN FRANCISCO PUB<br>30 VAN NESS AVENUE, 5TH FL |                                 | K RIVERA     | J. MUNOZ 09/19<br>CHECKED: DATE: | SHEET OF SI | LECEND AND                       |               | FILE NO.                           |
|                         |   | SAN FRANCISCO, CA 94102 -                       |                                 |              | UNEUNED, DATE:                   | OF          | LEGEND AND                       | ARRKEN        | IATIONS REV. NO.                   |

|       | A   B   C   D   E   | F      | I  | G I  | н   і  |  | J                           | К  |      |
|-------|---|--------|--|--|--|--|-----------------------------|--|------|
|       |   |        |  | GEI  | NERAL NOTES  | 5  |                             |  |      |
| 1.    | ENTERING INTO THIS CONTRACT WITH THE CITY INDICATES THAT THE CONTRACTOR HAS VISITED THE SITE, IS FAMILIAR WITH THE EXISTING CONDITIONS AND REVIEWED SAME WITH THE REQUIREMENTS OF THE CONTRACT DOCUMENTS.   | 23.    | THE FO<br>TO A F   | DLES OR VERTICAL ELEMENTS INS<br>LLOWING MINIMUM CLEARANCES:<br>IGH PRESSURE HYDRANT IS FIVE<br>T TO A LOW PRESSURE HYDRAN   | THE MINIMUM CLEARANCE (5) FEET. THE MINIMUM (                | BETWEEN A POLE   | E OR VERTICA                | L ELEMENT  |      |
| 2.    | THE CONTRACTOR IS RESPONSIBLE FOR CHECKING ALL CONTRACT DOCUMENTS AND FIELD CONDITIONS, AND<br>FOR CONFIRMING THAT THE WORK IS BUILDABLE AS SHOWN BEFORE PROCEEDING WITH THE WORK. THE<br>CONTRACTOR IS RESPONSIBLE FOR OBTAINING CLARIFICATION FROM THE CITY BEFORE PROCEEDING WITH THE<br>WORK IN QUESTION OR RELATED WORK. WRITTEN DIMENSIONS SHALL GOVERN. THE CONTRACTOR SHALL | 24.    |  | Y MONUMENTS MUST BE PROTEC<br>-5833 TO REPORT ANY MONUME   |  |  |                             |  |      |
| 3.    | VERIFY ALL DIMENSIONS PRIOR TO PROCEEDING WITH THE WORK.<br>THE CONTRACTOR SHALL VERIFY EXISTING FACILITIES IN THE FIELD, WHETHER OR NOT THEY ARE SHOWN ON  | 25.    | SHALL  | CTOR SHALL AVOID DAMAGING AN<br>NOTIFY CITY REPRESENTATIVE OF<br>ED THAT IS IN CONFLICT WITH P   | ANY GRANITE CURB NOT   | STING GRANITE C<br>IDENTIFIED ON TH                      | CURBS. CONTR<br>HE PLANS TO | ACTOR<br>BE RESET OR                             |      |
|       | THE DRAWINGS.   | 26.    | EXISTIN  | G GRANITE CURB SHALL ONLY B  | E REPLACED WITH CONCRE                                       |  |                             |  |      |
| 4.    | THE CONTRACTOR SHALL NOTIFY THE CITY REPRESENTATIVE IN WRITING OF CONFLICTS BETWEEN DRAWINGS PRIOR TO PROCEEDING WITH THE WORK IN QUESTION.   |        | NEW G  | PART OF CURB RAMP CONSTRU<br>RADE. IF EXISTING GRANITE CUR   | B IS DAMAGED, CONTRACTO                                      | OR SHALL NOTIFY  | Y CITY REPRES               | SENTATIVE.                                       |      |
| 5.    | THE CONTRACTOR IS RESPONSIBLE FOR WORKING AROUND AND PROTECTING ALL EXISTING FACILITIES<br>ADJACENT TO THE WORK AREA. THESE FACILITIES INCLUDE, BUT ARE NOT LIMITED TO, THE FOLLOWING:<br>CABLE CAR TRACKS, TREES, LANDSCAPING, HYDRANTS AND UTILITY POLES.   | 27.    | Y. IN THE EVENT COBBLESTONES ARE ENCOUNTERED AND TO BE REMOVED IN ANY STRE<br>THE CONTRACTOR SHALL REMOVE THEM FROM THE PROJECT SITE AS CITY PROPERTY.<br>AND DELIVERY OF EXISTING COBBLESTONES TO THE DESIGNATED AREAS, FROM THE PI<br>DONE AS INCIDENTAL WORK. |  |  |  |                             | SALVAGE. HAULING                                 |      |
| 6.    | THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING ALL WORK UNDER THIS CONTRACT TO AVOID REDUNDANCY BETWEEN PAVING/CURB RAMP WORK AND SEWER AND/OR WATER WORK OR OTHER UTILITY REQUIRED TRENCH RESTORATION.   | 28.    | CONTRA   | IN THE EVENT GROUNDWATER WELLS ARE ENCOUNTERED IN ANY STREET UNDER CONSTRUCTION, THE<br>CONTRACTOR SHALL BE RESPONSIBLE FOR GROUNDWATER WELL PRESERVATION (OR DESTRUCTION, IF<br>DESTRUCTION IS CALLED FOR). FOR PRESERVATION, THE CONTRACTOR SHALL EXERCISE CARE IN WORKING |  |  |                             |  |      |
| 7.    | CONFORM LINE SHALL BE FIVE (5) FEET BEYOND THE EXTENDED PROPERTY LINE UNLESS OTHERWISE INDICATED ON THE DRAWINGS OR AS DIRECTED BY THE CITY REPRESENTATIVE.   | 29.    | AROUND GROUNDWATER WELLS TO PREVENT DAMAGE.<br>. AT THE COMPLETION OF WORK, THE CONTRACTOR SHALL REMOVE ALL MARKS, STAINS AND BLEMISHES<br>RESULTING FROM CONSTRUCTION OPERATIONS THROUGHOUT THE CONTRACT.   |  |  |  |                             |  |      |
| 8.    | THE THICKNESS OF THE NEW ASPHALT CONCRETE WEARING SURFACE (ACWS) SHALL BE TWO (2) INCHES MINIMUM UNLESS OTHERWISE INDICATED ON THE DRAWINGS OR AS DIRECTED BY THE CITY REPRESENTATIVE.  | 30.    |  |  |  |  |                             |  |      |
| 9.    | CURB GRADE SHALL BE SIX (6) INCHES ABOVE THE ADJACENT PAVEMENT GRADE OR GUTTER GRADE UNLESS OTHERWISE INDICATED ON THE DRAWINGS OR AS DIRECTED BY THE CITY REPRESENTATIVE.  |        |  |  |  |  |                             |  |      |
| 10.   | WHEN EXISTING AND NEW ELEVATIONS ARE GIVEN FOR THE SAME POINT, THE CONTRACTOR SHALL<br>CONSTRUCT TO NEW ELEVATIONS. UNLESS OTHERWISE DIRECTED BY THE CITY REPRESENTATIVE, THE EXISTING<br>ELEVATIONS ARE FOR INFORMATION ONLY.  | 31.    | THE FOLLOWING ARE CONTACT PHONE NUMBERS:   |  |  |  |                             |  |      |
| 11.   | STANDARD DETAILS AND INFORMATION SHALL BE USED FOR ALL APPLICABLE CASES UNLESS OTHERWISE INDICATED.   |        | BLHP<br>DPW  | STREET LIGHTS<br>NEWS RACKS  | JOSEPH THOPPIL   | (415) 227-8<br>(415) 554-4                               | 1464                        | Streetlights@sfwater.or                          | g    |
| 12.   | CROSS SECTION CALL-OUTS ARE SHOWN ONLY ONCE ON THE DRAWINGS AND ARE TYPICAL FOR SIMILAR CONDITIONS UNLESS OTHERWISE INDICATED.  |        |  | SEWER REPAIR<br>STREET TREES (URBAN FOREST   | CATHERINE XU<br>RY)  | (415) 554–5<br>(415) 695–2<br>(415) 641–2                | 2096                        |  |      |
| 13.   | EXISTING CATCHBASIN GRADE SHALL BE ADJUSTED IN THE FIELD TO CONFORM TO NEW GUTTER GRADE.  |        | DT   | FIRE ALARM   | MIKE DENNING   | (415) 550-2  | 2718                        |  |      |
| 14.   | NEW GUTTER AND/OR PARKING STRIP SHALL CONFORM TO EXISTING PAVEMENT UNLESS OTHERWISE INDICATED.  |        | MTA  | MUNI OVERHEAD LINES<br>TRAFFIC SIGNAL SHOP<br>BUS SHELTERS   | JOHN ORKES<br>CLIFFORD SMETHURST<br>EDDIE TSUI<br>GAIL STEIN | (415) 554-9<br>(415) 554-9<br>(415) 550-2<br>(415) 646-2 | 9220<br>2742                |  |      |
| 15.   | THE LIMITS OF SIDEWALK RECONSTRUCTION SHOWN ON THE DRAWINGS ARE APPROXIMATE. THE CONTRACTOR<br>SHALL SAWCUT TO THE NEAREST FLAG/JOINT AND MATCH THE EXISTING SCORE PATTERN UNLESS OTHERWISE<br>INDICATED ON THE DRAWINGS OR AS DIRECTED BY THE CITY REPRESENTATIVE.   |        | SFWD   | BUSINESS HOURS REPAIRS<br>NON-BUSINESS HOURS REPAIR  |  | (415) 550-4965<br>(415) 550-4911<br>(415) 550-4925       |                             |  |      |
| 16.   | ALL UTILITY VAULTS AND PULL BOXES WITHIN THE SIDEWALK RECONSTRUCTION AREA SHALL BE ADJUSTED TO THE NEW GRADE.   |        | AT&T   | IDENTIFY LINES   | LYNN SCHUSSEL  | (650) 991-5  | 5630                        | LS4524@att.com                                   |      |
| 17.   | FOR ALL TRAFFIC SIGNAL PULL BOXES THAT ARE ROTATED, RELOCATED OR ADJUSTED, THE CONTRACTOR<br>SHALL CONTACT MTA TRAFFIC SIGNAL SHOP STEVE VANNUCCHI OR EDDIE TSUI AT LEAST THREE (3) DAYS  |        |  |  | MARIA TORRES<br>CAROL MITCHELL                               | (650) 216-2  |                             | MT1276@att.com<br>CM1463@att.com                 |      |
| 18.   | PRIOR TO SETTING THE PULL BOX AT THE NEW LOCATION AND/OR GRADE. ALL WORK SHALL MEET<br>REQUIREMENTS OF SFDPW STANDARD PLAN 87,201<br>THE 12-INCH WIDE GROOVED BORDERS (WARNING BANDS) ON CURB RAMPS SHALL NOT BE PART OF THE  |        | COMCAS   | ST   | JEFF CASTANEDA<br>DEREK NIPPE                                | (415) 377-1<br>(415) 503-4                               | 1921<br>4505                | Jeff_Castaneda@cable.                            | .com |
| 19.   | SLOPED RAMP AND WING SURFACES UNLÈSS OTHERWISE ÍNDICATED.   |        | PG&E   | SERVICE PLANNING   | JASON BUHAGIAR<br>DANA SOUZA<br>BILL RUSSO                   | (628) 256-5<br>(415) 757-8<br>(415) 695-3                | 3485                        | JH28@pge.com<br>D2GV@pge.com                     |      |
|       | THAN THE SPECIFIED FACE OF CURB (FOC) ELEVATION. CURB RAMPS WITHOUT GRADE BREAKS SHALL HAVE A MAXIMUM BACK OF CURB (BOC) ELEVATION OF 0.04 FEET HIGHER THAN THE FACE OF CURB (FOC) ELEVATION.   |        | CLEAR CHANNEL (BUS SHELTERS)   |  | NICHOLAS FAGUNDES<br>ASHLEY KIRCHNER                         | (925) 518-7  |                             | NicholasFagundes.ncs@                            |      |
| 20.   | ELEVATIONS SHOWN ON CURB RAMP DETAILS ARE MEASURED IN FEET AND ARE RELATIVE TO A LOCAL REFERENCE POINT (TOP OF FIRE HYDRANT IN MOST CASES) UNLESS OTHERWISE INDICATED.  |        |  |  | MARGEAUX CASILLAS  | (510) 446-7  |                             | AshleyKirchner.ncs@con<br>MargeauxCasillas@clear |      |
| 21.   | ASPHALT CONCRETE PATCHING AROUND NEW GUTTERS AND/OR PARKING STRIPS AT CURB RETURNS SHALL BE CONSIDERED AS INCIDENTAL WORK TO THE CURB RAMP BID ITEM.  |        |  | BOVENET (MFN FACILITIES)<br>ASTOUND)   | ALLEN LEHEW<br>KEN HAWKINS                                   | (415) 265-3<br>(925) 332-7                               |                             | Allen.Lehew@zayo.com<br>khawkins@wavebroadbo     |      |
| 22.   | CONCRETE BASE WORK SHOWN ON CURB RAMP DETAILS MAY OVERLAP WITH THE SAME WORK SHOWN ON PAVEMENT PLANS. THE CONTRACTOR SHALL COORDINATE OVERALL PAVING WORK TO AVOID PERFORMING DUPLICATE WORK.   |        | USPS   | MAILBOXES  |  | (415) 550-5  | 5248                        |  |      |
|       | REFERENCE INFORMATION           & FILE NO. OF SURVEYS   | R      | UREAU (  | )F Acting Section  | n Mgr: ERIC KJELSBERG  |  | GNED: DATE:                 |  | SC   |
|       |   | SCO OT | NGINEE   |  | u Mgr: FERNANDO CISNEROS                                     | DRAW   | N: DATE:                    |  |      |
| ). DA | E DESCRIPTION BY APP.<br>TABLE OF REVISIONS   | KS 30  | VAN NESS AVE   | CO PUBLIC WORKS<br>NUE, 5TH FLOOR<br>CA 94102 - 6028   | PATRICK RIVERA   | J. N<br>CHEC   | KED: DATE:                  |  | SH   |

TABLE OF REVISIONS THIS DRAWING WAS LAST MODIFIED: 09/11/19 14:38, BY: jmunoz

T OF SHEETS OF

| М                      |       | N             | 0              |   | Р                      |   |
|------------------------|-------|---------------|----------------|---|------------------------|---|
| м                      |       |               |                |   |                        | Drowing Path: S:\SH\JusteSi Sidewalk-level Bikewoy Pilot\Plans\R-G.dwg, Login: jmunoz Dimension Scale: 20 Xrefs: \\dpw.ci.sf.co.us\bookBOEFILES1\Data\SH\JusteSi Sidewalk-Level Bikewoy Pilot\Plans\DE2.TB_22x34_MAY 2019.dwg Plot Time: Wed, 11 Sep 2019 - 3:00pm Masurement Units are English |
|                        |       | 95%<br>NOT FO | VIEW<br>STRUCT | ION                                       |                        | idewalk-Level<br>3 - 3:00pm   |
| SIDEWALK-1<br>FOR BETT |       |               |                | CONTRACT NO<br>2752<br>DRAWING NO.<br>R-C | 5.<br>2J<br>5 <b>3</b> | 3:\SH\Josef\Si<br>11 Sep 2019   |
| GE                     | NERAL | NOTES         |                | FILE NO.<br>REV. NO.                      |                        | Drawing Path: {<br>Plot Time: Wed,  |
|                        |       |               |                |   |                        |   |

